BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Modified Schedule - B

BBMP/2021-22/RD/WORK_INDENT50951

NAME OF WORK: Comprehensive Development works in Ward No 13. Shettyhalli Sub Division

Sl. No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300-2. Earthwork excavation by manual means in Ordenary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Cum	43.36	152.00	Rupees One Hundred Fifty Two Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Cum	43.36	82.00	Rupees Eighty Two Only
3	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Cum	28.28	6084.00	Rupees Six Thousand Eighty Four Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl. No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
4	KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	22.62	5873.59	Rupees Five Thousand Eight Hundred Seventy Three and Fifty Eight Paise Only
5	KSRB 5-14.1 : Providing and constructing load bearing wall with 400x200x200mm solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	No	81.00	1005.39	Rupees One Thousand Five and Thirty Eight Paise Only
6	Providing and fixing Executive bench made out of sadarahally grey stone with hand supporter with three line finishing with arch design, with 100mm slab height 90 X length 150 X width 45cms (data rate) with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	50.00	20111.00	Rupees Twenty Thousand One Hundred Eleven Only
7	KSRB15-3.8 : Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	269.50	287.73	Rupees Two Hundred Eighty Seven and Seventy Two Paise Only
8	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	159.98	94.00	Rupees Ninety Four Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division